Last updated: 2023-12-06 Version 6.14

The assortment schedule aims to show where the supplier (technical consultant, contractor) or, where applicable, the client, of Trafikverkets's assignments/projects should search for material when investigating and planning (design) and procure material that is needed for the construction works in investments, reinvestments and maintenance. The tabs in the assortment schedule follow Trafikverkets's facility structure for railway and show decided supply routes for materials to the facility.

Materials which is classified as *technically approved material* (TGM) according to TDOK 2014:0307 follows from the columns "Material to be acquired from Trafikverket Logistik" and "Material to be acquired from a supplier based on a nationally procured framework agreement", and is <u>always</u> to be used. Technically approved material consists predominantly of rail- and IT related materials for Trafikverket's projects within railway and, in some cases, roads, which are supplied via Trafikverket Logistik. Terms for purchase and supplies from Trafikverket Logistik follows from *Förutsättningar vid beställning och leverans av tekniskt godkänt material* (TDOK 2012:195).

Material that is classified as *regulatory-controlled units* according to TDOK 2014:0307 and is published in TDOK/TRVINFRA follows the column "The project procures materials based on requirements". This material is procured by the project through requirements being set in procurement by the consultant and contractor respectively.

Version 6.14. means...

2023-12-04 New assortment 12.1 Property: Fresh air valves

Supply model for road paving in level crossings changed from 1st January 2024, see 6.1 Track and 10.2 Level crossing.

Explanatory text revised.

Version 6.13. means...

2023-06-21 Panel fence addes to 12.2 Fencing.

Version 6.12, means...

2023-02-23 Correction of information 9.5 Outbound 16.7 Hz medium voltage switchgear.

Version 6.11. means...

2022-10-07 Supply model changed, new assortment 8.3 Shunting yard braking system, 9.4 Converter/Transformer station, 9.5-9.7 Connection centre, Transformer station house, Switching station

Version 6.10. means...

2022-09-12 Supply model for road paving in level crossings changed, see 6.1 and 10.2.

Version 6.9. means...

2021-08-31 Supply model for station control system changed.

Version 6.8. means...

2021-06-28 Name of column three changed.

New assortment within electrical installations, 16.7 Hz Medium Voltage Switchgear.

Clarification station control system, electrical installations.

Version 6.7. means...

2020-06-09 Correction track, check rail removed.

Version 6.6. means...

2020-04-28 Correction supply model for track points.

Version 6.5. means...

2020-02-14 Clarification remote control system 9.10

Version 6.4. means...

2019-11-04 Anti trespass panels added to shunting-yard facilities

Version 6.3. means...

2019-10-19 Clarification how to handle missing assortment, Clarification Autotransformer,

Version 6.2. means...

2019-05-03 New assortment within electrical installations, 50 Hz Medium Voltage Switchgear for converter/transformation station, distribution centre and network station.

Clarifications 9.1 and 9.2. Clarifications 9.4-9.18. Clarification track without ballast 6.1.

Version 6.1. means...

2018-06-12 Corrected cable installation

TGM Regulatory-controlled units

New or modified material is to be developed is to developed according to TDOK 2014:0307

New or modified requirments specification is to be developed according to TDOK 2014:0307

			Material to be	Material to be	The project procures materials	Comments
			acquired from	acquired from a	based on a requirement	
			Trafikverket	supplier based		
			Logistik	on a nationally		
				procured		
				framework		
				agreement		
	Track superstructure					
6.1	Track	Rail	х			Determined supply model for rail is from Trafikverket with distribution via rail workshop in Sannahed as standard solution. Mobile flash-welding is primarily used when there is undercapacity at Sannahed or other reasons exist. Trafikverket shall always be contacted before mobile flash-welding is used.
		Sleeper	Х			
		Attachment	Х			For track without ballast, please contact Underhåll Teknik och Miljö.
		Joints	Х			Rails with glued joints: To be selected before joints for field mounting. Joints for field installation: Unglued joints selected before glued.
		Road paving in level	Х			
		crossings				Valid from 1st January 2024.
		Rail creep obstructions	Х			
		Ballast			х	
		Thermite welding kit			Х	
6.2	Points	Determined supply mode	I for track points is pr	efabrication as standa	ard solution.	
		Ballast			X	
		Attachment	Х			
		Rail	Х			
		Joint	Х			
		Sleeper	Х			
		Heavy unit	Х			
		Intermediate section	Х			
		Check rail	Х			
		Crossing	Х			
		Relaying device	Х			
		Inspection device	X			

		Locking device	X		
		Points heater	Х		Points heater and associated materials.
		Rail creep obstruction	Х		
		Snow protection	Х		
		Thermite welding kit		Х	

TGM Regulatory-controlled units

New or modified material is to be

developed is to developed according to TDOK 2014:0307

New or modified requirments specification is to be developed according to TDOK 2014:0307

		100112	014.0307	according to TDON 2014.0307	
		acquired from Trafikverket Logistik		The project procures materials based on a requirement	Comments
7	Track substrucure				
7.1	Embankment			Х	
7.2	Cutting			Х	
7.3	Culvert			Х	
7.4	Bridge			х	
7.5	Tunnel			х	

TGM

Regulatory-controlled units

New or modified material is to be

developed is to developed according to TDOK 2014:0307

New or modified requirments specification is to be developed according to TDOK 2014:0307

			Material to be acquired from Trafikverket Logistik	The project procures materials based on a requirement	Comments
8	Shunting-yard facilities				
8.1	Platform and loading quay			х	
8.2	Platform crossing	Surfacing		Х	
		Substructure		X	
		Superstructure		Х	
		Gate/Stile		X	
		Control equipment	Х		
		Power supply	Х		
		Control and inspection	Х		
		Transmission (cable)	Х		
		Lifting barrier device	х		
		Signal for passenger/truck traffic	х		
8.3	Shunting yard braking	Beam rail brake		Х	
	system	Spiral brake	Х		Reparations included.

		Piston brake	x *	X**	* Applies when the maintenance contract for Hallsberg shunting yard is next procured, preliminary contract start 2025-04-01. ** Expires when the maintenance contract for Hallsberg shunting yard is next procured.
8.4	Track barrier		Х		
8.5	Buffer	Concrete		Х	
		Other	Х		
8.6	Brake testing facility			Х	
8.7	Wagon weighbridge			Х	
8.8	Turnplate			х	
8.9	Anti trespass panels		Х		

TGM Regulatory-controlled units

New or modified material is to be

developed is to developed according to TDOK 2014:0307 New or modified requirments specification is to be developed according to TDOK 2014:0307

			Material to be	Material to be	The project procures materials	Comments
			acquired from		based on a requirement	
			Trafikverket	supplier based	acca cir a requirement	
			Logistik	on a nationally		
			Logiotiik	procured		
				framework		
				agreement		
				agreement		
9	Electrical installations				!	
9.1	Catenary	Tensioning	Х			
		Line circuit-breaker	х			
		Insulator	Х			
		Cable	Х			
		Line bridge	х			
		Pole	Х			
		Autotransformer including footing and building	х			3, 5 & 6 MVA transformer, building AT including selectable options, also hoists for footing.
		Booster transformer	Х			100,5 & 158 kVA
		Wire, line	х			
		Cantilever	Х			
		Facting for pale	· ·			Agreement for prefabrication exists, non-manadatory. Sub-ordering via Trafikverket.
		Footing for pole	х		х	For projects and measures with minor requirements, footings (1 - 5 pcs depending on item number) can be purchased from Ma. Larger quantities to be purchased by the contractor directly.
9.2	Auxiliary power line		Х			
		Distribution transformer	Х			10 - 500 kVA
	Supply line				Х	
9.4	Converter/Transformer	Spare parts	Х			
	station	Outbound 16.7 Hz single- phase Medium Voltage Switchgear	Х			Also see 9.5-9.7.
		Incoming 50 Hz Medium Voltage Switchgear	х			

1 1	Station control system		Х	
	Batteries	X		
	Standby power plant	X		Also see 9.11.
	UPS	Х		
	Rectifier frame, direct	X		
	current-system, power			
	supply (DC)			
	Catenary test device	Х		
	Binders	Х		
	Emergency disconnector over ethernet	х		Also see 9.5-9.7.
9.5 - Connection centre 9.7 Transformer station hous Switching station	Outbound 16.7 Hz single- e phase Medium Voltage Switchgear	х		Also applies to spare parts for switchgear H2000 and MH switchgear.
	Station control system		x	
	Batteries	Х		
	Standby power plant	Х		Also see 9.11.
	UPS	Х		
	Rectifier frame, direct current-system, power supply (DC)	Х		
	Catenary test device	Х		
	Binders	Х		
	Emergency disconnector over ethernet	х		Preliminary orderable from 2023-05-01 with delivery times according to agreement.
9.8 - Distribution centre 9.9 Network station	Incoming 50 Hz Medium Voltage Switchgear	X		
	Medium voltage distribution transformer	Х		2 MVA
	Batteries	Х		
	Standby power plant	Х		Also see 9.11.
	UPS	Х		
	Rectifier frame, direct current-system, power supply (DC)	Х		
9.10 Remote control system	RTU	Х		
9.11 Technical building	Batteries	Х		
	Standby power plant	х		Power plants up to and including 120 kVA are covered. Standby power plants larger than 120 kVA may be procured externally, but must meet "TDOK 2014:0785 BVS 543.14610 Elkraftanläggningar Kravspecifikation för reservkraftstationer".
	UPS	Х		

		Rectifier frame, direct current-system, power supply (DC)	х		
9.12	Train and locomotive heating plant 16.7 Hz		х		
9.13	Lighting installations		x (batteries)		
		Shunting-yard lightning	х		Shunting-yard lightning and associated materials.
		Tunnel lightning		Х	
		Platform lightning		х	
9.14	Points heater		х		Points heater and associated materials.
9.15	Distribution network <1000 V			х	
9.16	Operational control centre,	Batteries	х		
9 18	power supply Standby power plant	Standby power plant	Х		Also see 9.10-9.11.
00	Computer centre, power	UPS	Х		
	,	Rectifier frame, direct current-system, power supply (DC)	Х		

TGM

Regulatory-controlled units

developed is to developed according to TDOK 2014:0307

New or modified material is to be New or modified requirments specification is to be developed according to TDOK 2014:0307

				014.0001	2017.0001	
					The project procures materials	Comments
					based on a requirement	
				supplier based		
			Logistik	on a nationally		
				procured		
				framework		
				agreement		
	Signal installations					
10.1	Track coil (beacon) group		х			
10.2	Level crossing	Substructure			х	
		Road paving	Х			Valid from 1st January 2024.
		Surfacing			х	
		Portal			х	
		Control equipment	х			
		Power supply	х			
		Control and inspection	х			
		Transmission (cable)	х			
		Lifting barrier device	х			
		Signal and board	х			
	Positioning system	Rectifier-track line	х			
	Signal		X			
	Switchgear RBC and line blocking		x (maintenance)	x (newbuilding)		

10.6	Shunting switchgear	AlisterCargo		x* (maintenance) x** (maintenance) (newbuilding			* Refers to common switchbox spare parts and used relay sets for older installations						
		NovoCargo		x* (maintenance)	x** (maintenance)		** Support and maintenance agreement exists incl. spare parts apart from those supplied by Trafikverket.						
		BV PLC, 3A, 3B		x (maintenance)		x (maintenance)	T						
10.7	Board			х									
10.8-	Train control system	ARGUS				Х							
11		EBICOS TMS				Х							
		EBICOS 900 & EBIC	EBICOS 900 & EBICOS NT										
			PC platform			Х							
			APN platform	x			Not new construction						
		Sub-station					-						
			EBISAT 890	X									
			Siemens S5	Х			Not new construction						
			Siemens S7	х									
			JZA 700			Х							
			JZA 41			х							
		_	RTU			Х							

TGM

Regulatory-controlled units

New or modified material is to be developed is to developed according to TDOK 2014:0307

New or modified requirments specification is to be developed according to TDOK 2014:0307

					The project procures materials	Comments
			•		based on a requirement	
			Trafikverket	supplier based		
			Logistik	on a nationally		
				procured		
				framework		
				agreement		
11	Telecom&IT installations	1				
11.1		FUES, Servo, SATT,	x (maintenance)	x* (new building)		Trafikverket's framework agreement for
		Schenck, KIKA and other				deliveries of detectors.
		detektors.				
		Detector presentation			x	
		DPC II				
		Detector kiosk	Х			Power supply for technical buildings
						intended for radio base stations and
						detector installations.
11.2	Cable installation	Metal cable, fibre-optic	Х			Product that are item-identified in the
		cable, control cable, pair				Material catalogue are purchased via
		cable, KOAX, single				Trafikverket. The project organisation is
		conductor incl. accessories as				free to choose other products for supply solutions on the basis of specifications.
		microduct assemblies,				solutions on the basis of specifications.
		splicingbox/cabinet, fiber				
		joint closure, patch				
		cable, connectors etc.				
11.3	Radio installation	Radio mast		X		
						Trafikverket's framework agreement for
						installations of MobiSir radio masts.
		Radio base station		Х		Trafikverket's framework agreement for
						detector and radio installation buildings.
1	I					

i	ı	Other media a suria servi					<u>, </u>
		Other radio equipment				Х	
			Antennae, cables,			Х	
	<u> </u>		contacts				
			Radio link	Х			
			Tunnel radio repeater	x*	x*, x**		* Spare parts for older versions available at Trafikverket, spare parts for the newest version is availble through the framework agreement. ** Framework agreement for radio repeaters in tunnels and buildings, to be used.
11.4	Signal telephone					х	
11.5	Telecom centre					х	
11.6	Telecom station facility			x (maintenance)		x (new building)	
11.7	Telecom transmission facility		Pressure protection equipment	х			
			Pressure protection monitoring equipment		х		
11.8	Dynamic and fixed sign		Mitron signs	Х			
			TFT signs	Х			
			RGB-signs	Х			
			Terminals and prator units	Х			
	Loudspeaker system			Х			
11. 10	Clocks			Х			

TGM

Regulatory-controlled units

New or modified material is to be developed is to developed according to

New or modified requirments specification is to be developed according to TDOK 2014:0307

					2014:0307	according to TDOK 2014:0307	
					Material to be	The project procures materials based on a requirement	Comments
12	Other installations		•		•		
12.1	Property	Building					
			Cabinet	Х			
			Technical building, kiosk, hut	x (detector)	x* (MobiSir)	x (maintenance)	* Refers to framework agreement - Technical building for detectors and radio installations (MobiSir).
			Fire safety equipment			Х	
		Fresh air valves		Х			Used for noise protection measures in properties along Trafikverket's facility.
12.2	Fencing					X	
		Panel fence		Х			
12.3	Ductwork					x	
12.4	Rail lubrication device					х	
12.5	Snow fence					Х	
12.6	Road					х	
	Dewatering, pump system					Х	
12.8	Surveillance cameras			Х			

12.9	Cable installation	Metal cable, fibre-optic	Х		Product that are item-identified in the Material
		cable, control cable, pair			catalogue are purchased via Trafikverket. The
		cable, KOAX, single			project organisation is free to choose other
		conductor incl.			products for supply solutions on the basis of
		accessories as			specifications.
		microduct assemblies,			
		splicingbox/cabinet, fiber			
		joint closure, patch			
		cable, connectors etc.			